

STRUCTURAL NOTES:

- THIS NON POROUS SYSTEM HAS BEEN VERIFIED FOR COMPLIANCE IN ACCORDANCE WITH THE 2020 (SEVENTH EDITION) OF THE FLORIDA BUILDING CODE (FBC) . THIS SYSTEM SHALL NOT BE INSTALLED IN THE HIGH VELOCITY HURRICANE ZONE (MIAMI-DADE/ BROWARD COUNTIES), NOR ESSENTIAL FACILITIES. THE ADEQUACY FOR IMPACT, DEFLECTION AND FATIGUE RESISTANCE HAS BEEN VERIFIED IN ACCORDANCE WITH THE ABOVE REFERENCED CODE, AND AS PER TAS 201, TAS 202 and TAS 203 PROTOCOLS AND ASTM E330-02, ASTM E1886-05 AND ASTM E1996-05. SEE LIST OF REPORTS ON SHEET 1/2.
- DESIGN PRESSURE REQUIREMENTS OF A SPECIFIC SITE SHALL BE DETERMINED BY OTHERS IN CONFORMANCE TO SECTION 1609 OF THE FBC FOR A BASIC WIND SPEED (ALLOWABLE STRESS DESIGN) AS REQUIRED BY THE JURISDICTION WHERE THE SYSTEM WILL BE INSTALLED. ULTIMATE DESIGN LOADS (UD) DETERMINED BY ASCE 7-16 SHALL BE REDUCED TO ALLOWABLE STRESS DESIGN LOADS (ASD) BY MULTIPLYING THE UD BY 0.6. TO COMPARE THEM TO THE ASD PRESSURE RATINGS SHOWN ON SHEET 1 AND 2. USE OF DIRECTIONALITY FACTOR $K_d=0.85$ IS ALLOWED.
- IMPACT AND FATIGUE RESISTANCE HAS BEEN DETERMINED IN ACCORDANCE WITH THE FBC SECTION 1609.1.2 MISSILE TYPE "D" AS LISTED HEREIN.
- NO 33-1/3% INCREASE IN ALLOWABLE STRESS INCREASE HAS BEEN USED IN THE DESIGN OF THIS PRODUCT.
- 5a. THIS PRODUCT EVALUATION DOCUMENT (PED) DETAILED HEREIN IS GENERIC AND DOES NOT PROVIDE INFORMATION FOR A SPECIFIC SITE. IF SITE CONDITIONS DEVIATE FROM THE CONDITIONS DETAILED HEREIN, A LICENSED ENGINEER OR REGISTERED ARCHITECT SHALL PREPARE SITE SPECIFIC DOCUMENTS TO BE USED IN CONJUNCTION WITH THIS DOCUMENT.
- 5b. THE CONTRACTOR AND / OR PERMIT HOLDER IS TO BE RESPONSIBLE FOR THE SELECTION, PURCHASE AND INSTALLATION OF THIS SYSTEM, INCLUDING VERIFYING THE ADEQUACY OF THE EXISTING STRUCTURE TO WITHSTAND THE NEW SUPERIMPOSED LOADS SHOWN BELOW AND THE SOUNDNESS OF THE STRUCTURE WHERE THE SYSTEM IS TO BE ATTACHED TO INSURE PROPER ANCHORAGE.
- 5c. SITE SPECIFIC PROJECTS SHALL BE PREPARED BY A FLORIDA LICENSED ENGINEER OR ARCHITECT WHO WILL BECOME THE ENGINEER OF RECORD (EOR) FOR THE PROJECT AND WHO WILL BE RESPONSIBLE FOR THE PROPER USE OF THE PED ENGINEER OF RECORD, ACTING AS A DELEGATED ENGINEER TO THE PED ENGINEER SHALL SUBMIT TO THIS ENGINEER THE SITE SPECIFIC DRAWINGS FOR REVIEW.
- THIS PED SHALL BEAR THE DATE AND ORIGINAL SEAL OF THE PROFESSIONAL ENGINEER OF RECORD THAT PREPARED IT.
- THIS SYSTEM MAY ALSO BE INSTALLED HORIZONTALLY FOLLOWING INSTALLATION DETAILS SHOWN HEREIN.
- THIS WIND ABATEMENT SYSTEM IS INTENDED FOR USE ONLY DURING HURRICANE OR OTHER TROPICAL STORM WARNINGS. SEASONAL OR PERMANENT INSTALLATION OR STORAGE OF THIS WIND ABATEMENT SYSTEM IN AREAS OF PROLONGED EXPOSURE TO DIRECT SUNLIGHT OR OTHER WEATHERING CONDITIONS MAY CAUSE MATERIAL DETERIORATION OR OTHERWISE INHIBIT THEIR ADEQUACY AS AN IMPACT RESISTANT SYSTEM.
- LIMITATIONS OF USE
PER FBC 2020 NO MINIMUM SEPARATION FROM GLASS IS REQUIRED.
THE MAXIMUM SIZE SHALL BE 60 PSF MAX. PRESSURE @216 INCHES MAXIMUM SPAN. SEE TABLES ON SHEET 1/2.
- RESERVED.
- ALL SCREWS TO BE STAINLESS STEEL 304 OR 316 SERIES OR CORROSION RESISTANT COATED CARBON STEEL WITH A 50 KSI YIELD STRENGTH AND A 90 KSI TENSILE STRENGTH.
- ALL BOLTS TO BE ASTM A307, GALVANIZED OR 304 SERIES STAINLESS STEEL WITH A MINIMUM 36 KSI YIELD STRENGTH.
- ANCHORS TO STRUCTURE (WALL / FLOOR / CEILING / SYSTEM) SHALL BE INSTALLED PER MANUFACTURERS' RECOMMENDATIONS AND AS FOLLOWS:
 - CONCRETE BLOCK MASONRY (ASTM C-90)
TAPCON ANCHORS (ITW BUILDEX) OR PANELMATE MALE & FEMALE FASTENERS (ELCO TEXTRON) - 1/4 IN. DIA.
I. MINIMUM EMBEDMENT INTO HOLLOW CONCRETE BLOCK MASONRY FOR TAPCON ANCHORS AND ELCO PANELMATES IS 1 1/4 IN., FILLED MASONRY EMBEDMENT IS 1 3/4". NO EMBEDMENT INTO STUCCO SHALL BE PERMITTED.
II. PAVERS, BRICKS OR OTHER PRE-CAST PRODUCTS LOCATED ON THE EXISTING STRUCTURE WALL OR FLOOR SHALL HAVE ANCHORS OF SUFFICIENT LENGTH TO PROPERLY ATTACH TO THE PRIMARY STRUCTURE BEHIND IT.
III. MINIMUM EDGE DISTANCE = 3.0"
 - POURED CONCRETE ($f'_c=3000$ PSI MIN.)
TAPCON ANCHORS (ITW BUILDEX) OR PANELMATE MALE & FEMALE FASTENERS (ELCO TEXTRON) - 1/4 IN. DIA.
I. MINIMUM EMBEDMENT INTO POURED CONCRETE FOR TAPCON ANCHORS AND ELCO PANELMATES IS 1 3/4 IN. NO EMBEDMENT INTO STUCCO SHALL BE PERMITTED. SCREWS TO BE 1/4"-20 X 1 3/4" FOR STUCCO, 1 1/4" WITH NO STUCCO.
II. PAVERS, BRICKS OR OTHER PRE-CAST PRODUCTS LOCATED ON THE EXISTING STRUCTURE WALL OR FLOOR SHALL HAVE ANCHORS OF SUFFICIENT LENGTH TO PROPERLY ATTACH TO THE PRIMARY STRUCTURE BEHIND IT.
III. MINIMUM EDGE DISTANCE = 3.0"
 - WOOD (Nominal 2x4(min) "Southern Pine" SG=0.55 OR GREATER)
TAPCON ANCHORS (ITW BUILDEX) DIA. OR PANELMATE MALE & FEMALE FASTENERS (ELCO TEXTRON) - 1/4 IN.
I. MINIMUM EDGE DISTANCE = CENTER OF 2" NOMINAL LUMBER (APPROX. 3/4"). MINIMUM EMBEDMENT = 1-1/2"
- MAXIMUM DESIGN PRESSURE VERSUS PANEL SPAN SHOWN ON SHEET 1/2
- SCREEN PANEL'S MANUFACTURER LABEL SHALL BE PLACED ON A READILY AND VISIBLE LOCATION ON THE PANEL. ONE LABEL SHALL BE PLACED FOR EVERY OPENING. LABEL SHALL READ AS FOLLOWS:
HURRICANE FABRIC LLC
PO BOX 50153; CLAYTON, MO 63105
FLORIDA PRODUCT APPROVAL NUMBER: FL-XXXX. OPENING NO.: XX
- THIS DOCUMENT IN ITS ENTIRETY WILL BE CONSIDERED INVALID IF IT IS ALTERED BY ANY MEANS.

RETENTION CLIP END CONNECTOR:

RHODIA ENGINEERING PLASTICS - POLYAMIDE 66

FABRIC SPECIFICATION:


FIBER CONTENT: TEXTILE FABRIC
CONSTRUCTION: 20 X 20 WEAVE
FINISH: RESIN COATED
WEIGHT (ASTM D-3776): 9.0 -OZ/SQUARE YARD
TENSILE STRENGTH (GRAB METHOD, ASTM D -4632): WARP - 570 lbs., WEFT - 570 lbs.
BURST STRENGTH (ASTM D - 3786): 1,000 PSI
ABRASION RESISTANCE (ASTM D -4886) 95% STRENGTH RETAINED

SEWING:

ONLY SEWING IS AT SPLICE

EDGES:

NO SEWING AT EDGES



FASTENER SPACING OF A SINGLE UNIT SCREEN FOR ANY LENGTH ATTACHED WITH 3/8" DROP-IN ANCHOR WITH SIDEWALK BOLT (INCHES)

SCREEN SPAN	FILLED CMU (1900 PSI)				CONCRETE (4000 PSI)				HOLLOW CMU				TIMBER			
	PRESSURE (PSF)				PRESSURE (PSF)				PRESSURE (PSF)				PRESSURE (PSF)			
	60	50	40	30	60	50	40	30	60	50	40	30	60	50	40	30
4'-0"	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12
6'-0"	12	12	12	12	12	12	12	12	12	12	12	12	9	11	12	12
8'-0"	12	12	12	12	12	12	12	12	12	12	12	12	6	7	8	10
10'-0"	12	12	12	12	12	12	12	12	10	12	12	12	5	6	7	9
12'-0"	10	12	12	12	12	12	12	12	9	10	12	12	5	5	6	8
14'-0"	9	10	12	12	10	11	12	12	8	9	10	12	-	4	5	6
16'-0"	8	9	10	12	8	10	11	12	7	8	9	11	-	-	4	6
18'-0"	7	8	9	11	8	9	10	12	6	7	8	10	-	-	4	5

FASTENER SPACING OF A SINGLE UNIT SCREEN FOR ANY LENGTH ATTACHED WITH 1/4" ELCO PANELMATE PRO, MALE & FEMALE (INCHES)

SCREEN SPAN	FILLED CMU (1900 PSI)				CONCRETE (4000 PSI)				HOLLOW CMU				TIMBER			
	PRESSURE (PSF)				PRESSURE (PSF)				PRESSURE (PSF)				PRESSURE (PSF)			
	60	50	40	30	60	50	40	30	60	50	40	30	60	50	40	30
4'-0"	12	12	12	12	12	12	12	12	11	12	12	12	10	11	12	12
6'-0"	11	12	12	12	12	12	12	12	8	9	10	12	7	8	9	12
8'-0"	7	8	10	12	8	9	11	12	5	6	7	9	5	5	6	8
10'-0"	6	7	8	10	7	8	9	11	4	5	6	7	-	4	5	6
12'-0"	5	6	7	9	6	7	8	9	-	4	5	6	-	-	4	6
14'-0"	4	5	6	7	5	5	6	8	-	-	4	5	-	-	-	5
16'-0"	-	5	5	6	4	5	6	7	-	-	-	5	-	-	-	4
18'-0"	-	-	5	6	-	4	5	6	-	-	-	4	-	-	-	-

EVALUATION BASED ON:
FENESTRATION TESTING LABORATORY, INC

LAB NO.: 6418 DATED 12/7/2010

ASTM E330-02 - UNIFORM STATIC LOADS
ASTM E1886-05 & ASTM E1996-05 - LARGE MISSILE TYPE "D" IMPACT RESISTANCE & CYCLIC LOADING PERFORMANCE

LAB NO.: 5804 DATED 01/13/2009

TAS 202 - UNIFORM STATIC LOADS
TAS 201, TAS 202 - LARGE MISSILE IMPACT RESISTANCE & CYCLIC LOADING PERFORMANCE

LIST OF REPORTS


John H. Kampmann Jr., PE
FL License #: 47516
DATE:

WWW.MEENGINEERS.COM CA #6752
MEEA ENGINEERS, INC.
 5656 Lawton Drive
 Sarasota, Florida 34233
 (941) 922-3854 CA-6072

REV.	DESCRIPTION
1	xx/xx/xx--RESERVED


HURRICANE FABRIC LLC
 PO BOX 50153
 CLAYTON, MO 63105
 PHONE: (239)899-0099
 WWW.HURRICANEFABRIC.COM

2020 FBC (NON-HIGH VELOCITY HURRICANE ZONE) 7TH EDITION
 Project Name: HURRICANE FABRIC LLC
 Description: ASTRO GUARD Wind Abatement System
 Drawn: JK
 Project #: 20-0226
 Scale: NTS
 Date: 10/3/20
 Sheet No.: 1/2




TYPICAL TWO-SIDED INSTALLATION
VERTICAL OR HORIZONTAL INSTALLATION - N.T.S.

NOTE:
PANELS CAN BE ATTACHED ON THREE OR FOUR SIDES.
FOR FOUR SIDE ATTACHMENT THE SPAN IS IN THE SHORT DIMENSION BETWEEN FASTENERS



SECTION A-A (OPTION 1)
INSIDE MOUNT INSTALLATION - N.T.S.




SECTION A-A (OPTION 2)
OUTSIDE MOUNT INSTALLATION - N.T.S.

LOADS ON EXISTING STRUCTURE FROM SCREEN SYSTEM
TX = PARALLEL LOADS (PLF)


SPAN (INCHES)	PRESSURE (PSF)						
	60	55	50	45	40	35	30
216	1134	1070	1004	936	866	792	714
192	1020	962	903	842	778	712	642
168	905	854	801	747	690	631	570
144	744	702	659	614	568	519	469
120	651	615	577	538	497	455	410
96	553	521	489	456	422	386	348
72	353	333	312	291	269	246	222
48	254	240	225	210	194	178	160

LOADS ON EXISTING STRUCTURE FROM SCREEN SYSTEM
TY = PERPENDICULAR LOADS (PLF)


SPAN (INCHES)	PRESSURE (PSF)						
	60	55	50	45	40	35	30
216	540	495	450	405	360	315	270
192	480	440	400	360	320	280	240
168	420	385	350	315	280	245	210
144	360	330	300	270	240	210	180
120	300	275	250	225	200	175	150
96	240	220	200	180	160	140	120
72	180	165	150	135	120	105	90
48	120	110	100	90	80	70	60



BOTTOM MOUNTING CLIP DETAILS
INSIDE OR OUTSIDE MOUNT INSTALLATION - N.T.S.



TOP MOUNTING CLIP DETAILS
INSIDE OR OUTSIDE MOUNT INSTALLATION - N.T.S.



2020 FBC (NON-HIGH VELOCITY HURRICANE ZONE) 7TH EDITION

ASTRO GUARD
Wind Abatement System

Drawn: JK
Project #: 20-0226
Scale: NTS
Date: 10/3/20
Sheet No.:

John H. Kampmann Jr., PE
FL License #: 47516
DATE:

REV.	DESCRIPTION
1	xx/xx/xx-RESERVED

HURRICANE FABRIC LLC
PO BOX 50153
CLAYTON, MO 63105
PHONE: (239) 699-0099
WWW.HURRICANEFABRIC.COM